

OPEN TENDER NOTICE

For MW (Cons) for SR to Devidol at Jaysagar, Sivasagar, Assam (2018-19)

REFERENCE NO. F. NO : 2/13-W(K)/2018-19 -3505 #23 5/19



सत्यमेव जयते

GOVERNMENT OF INDIA
MINISTRY OF CULTURE
ARCHAEOLOGICAL SURVEY OF INDIA
GUWAHATI CIRCLE, GUWAHATI

K. *[Signature]* 23/01/19
अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwahati-01

[Signature]

Section-1

Table – A: Time and Work Frame

FOR EXECUTION OF WORK – MW (Cons) for SR to Devidol at Jaysagar, Sivasagar, Assam (2018-19)

Manual bids shall not be accepted

CRITICAL DATE SHEET

1.	Date of issue of Tender	23.01.2019 at 17.30 Hrs.
2.	Bid Document Download/Sale Start Date	24.01.2019 from 10:00 Hrs.
3.	Date of Pre Bid Conference For clarifying issues and doubts, if any, about specification of material and services projected in Bid document.	N.A.
4.	Start date for submission of filled-in tender document.	24.01.2019 from 10.30 Hrs.
5.	Bid Submission End Date	02.02.2019 up to 12.00 Hrs.
6.	Date of opening of Technical/Financial bid	04.02.2019 at 12.05 Hrs.
7.	Date of meeting with Bidders post Technical Bid opening for presentation and Document Verification	N.A.
8.	Validity of Bid	120 Days.


R. - अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी
Guwahati Circle, Assam

Dear Sir,


The Archaeological Survey of India invites online Bids in the prescribed form **under the Two Bid system** i.e. Technical Bid and Financial Bid for the Execution of work: – **For MW (Cons) for SR to Devidol at Jaysagar, Sivasagar, Assam (2018-19)**

1. The system of e-tendering shall be adopted, comprising of Technical Bid and the Financial Bid.
Document Download: Tender documents may be downloaded from CPPP site <https://eprocure.gov.in/eprocure/app> and www.asiguwahaticircle.gov.in as per the schedule as given in CRITICAL DATE SHEET.
Technical Bid should, inter alia, contain all technical details of services and solutions to be provided along with such documentary proofs. Financial Bid should, inter alia, indicate item-wise price and other commercial/financial terms against the items mentioned in the Technical Bid.
2. **Bid Submission:**
Applicants/intending or interested Bidders are invited to submit their proposal after carefully reading the Request for Proposal (RFP) by providing (a) Technical Bid, and (b) Financial Bid, separately, clearly mentioning (i) 'Technical Proposal', and (ii) 'Financial Proposal' respectively. Such proposals are to be submitted within the stipulated date and time as mentioned in the Bid document **as given in CRITICAL DATE SHEET.**
Bids shall be submitted online only at CPPP website: <https://eprocure.gov.in/eprocure/app> Bid documents may be scanned with 100 dpi with black and white option which helps in reducing size of the scanned document.
3. **Earnest Money Deposit:**
The Hard Copy of original instruments in respect of cost of earnest money must be delivered to the Superintending Archaeologist, Archaeological Survey of India, Guwahati on or before Bid opening date/time as mentioned in critical date sheet. Tenderer shall likely to be liable for legal action for non-submission of original payment instrument like DD etc. against the submitted Bid.
The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization, National Small Industries Corporation (NSIC) or Ministry of Culture.
4. **The EMD be submitted separately as under:**
 1. Tender inviting authority in the **Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle.**
 2. Time period for the execution of work/supply of materials shall be completed within **180 days** from the issue of the work order.
5. **Estimated Cost of Tender: ₹ 22,33,828/-** (Rupees Twenty Two lakh Thirty Three Thousand Eight Hundred & Twenty Eight only)

Address for communication, are as given below:-

Contact Details:

Contact Person	1. Shri K.Amarnath Ramakrishna, Superintending Archaeologist. 2. Shri S. K. Dutta, Dy. Suptdg. Archaeological Engineer.
Address for communication	Office of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, 5 th Floor, West End Block, HOUSEFED Complex Beltola -Basistha Road, Guwahati -781006


अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwahati-०१

F. No. 2/13-W(K)/2018-19
Government of India
Office of the Superintending Archaeologist
Archaeological Survey of India
Guwahati Circle
5th Floor, West End Block, HOUSEFED Complex
Beltola -Basistha Road, Guwahati -781006


TENDER DOCUMENT (Financial Bid)

For the Work: **MW (Cons) for SR to Devidol at Jaysagar, Sivasagar, Assam (2018-19)**

Estimated Cost : ₹ 22,33,828/- (Rupees Twenty Two lakh Thirty Three Thousand Eight Hundred & Twenty Eight only)

READ TERMS AND CONDITION BEFORE FILLING UP THE SCHEDULE.SIGN ON ALL PAGES.
Open Tender for execution of complete work.

Item No.	Item Of Work	Quantity	Unit
1	Provision for 25 mm to 30 mm thick Lime-Sand- Surkhi Plaster (1:1:1)in two coats mixing with organic materials to the walls and roof of the monument after removal of old dead plastering including raching the joints and cleaning, washing etc and preparing the surface for replastering Mukhamandapa (Outside wall).	251	Sqm
2	Renewing lime concrete in (1:1:1) of with 50% mortar lime, surkhi and brick aggregate mixing with organic materials including beating upto 7 days to the floor and roof after removal of old damaged decomposed and deteriorated lime concrete/rubbish etc..	1.1	Cum
3	Provision for stitching of crakes of the monument after cleaning, brushing & washing of the crakes.	26	Rmt
4	Removing brick work manually including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In Cement mortar.	57.00	Cum
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	16	Cum
6	Brick on edge flooring/pathway with 80% of new bricks of class designation 7.5 & 20% of old usable bricks on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks 1:4 (1 cement : 4 coarse sand).	178.00	Sqm


23/01/19
अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwahati-01