

OPEN TENDER NOTICE

**For MW (Conservation) Annual Repair to David Scott's Memorial at Cherapunji, Meghalaya
(2018-19)**

REFERENCE NO. F. NO : 2/14-W(C)/2018-19- 1575 # 419 168



सत्यमेव जयते

GOVERNMENT OF INDIA
MINISTRY OF CULTURE
ARCHAEOLOGICAL SURVEY OF INDIA
GUWAHATI CIRCLE, GUWAHATI

Section-1

Table – A: Time and Work Frame

FOR EXECUTION OF WORK – MW (Conservation) Annual Repair to David Scott's Memorial at Cherapunji, Meghalaya (2018-19)

Manual bids shall not be accepted

CRITICAL DATE SHEET

1.	Date of issue of Tender	04.09.2018 at 17.30 Hrs.
2.	Bid Document Download/Sale Start Date	05.09.2018 from 10.00 Hrs.
3.	Date of Pre Bid Conference For clarifying issues and doubts, if any, about specification of material and services projected in Bid document.	N.A.
4.	Start date for submission of filled-in tender document.	05.09.2018 from 10.30 Hrs.
5.	Bid Submission End Date	11.09.2018 up to 12.00 Hrs.
6.	Date of opening of Technical/Financial bid	12.09.2018 at 12.05 Hrs.
7.	Date of meeting with Bidders post Technical Bid opening for presentation and Document Verification	N.A.
8.	Validity of Bid	120 Days.

K. [Signature] 03/09/18
अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Cooch Behar Circle, Gauhati, Assam


Dear Sir,

1. The Archaeological Survey of India invites online Bids in the prescribed form **under the Two Bid system** i.e. Technical Bid and Financial Bid for the Execution of work: – **MW (Conservation) Annual Repair to David Scott's Memorial at Cherapunji, Meghalaya (2018-19)**
2. The system of e-tendering shall be adopted, comprising of Technical Bid and the Financial Bid. **Document Download: Tender documents may be downloaded from CPPP site <https://eprocure.gov.in/eprocure/app> and www.asiguwahaticircle.gov.in as per the schedule as given in CRITICAL DATE SHEET.**
Technical Bid should, inter alia, contain all technical details of services and solutions to be provided along with such documentary proofs. Financial Bid should, inter alia, indicate item-wise price and other commercial/financial terms against the items mentioned in the Technical Bid.
3. **Bid Submission:**
Applicants/intending or interested Bidders are invited to submit their proposal after carefully reading the Request for Proposal (RFP) by providing (a) Technical Bid, and (b) Financial Bid, separately, clearly mentioning (i) 'Technical Proposal', and (ii) 'Financial Proposal' respectively. Such proposals are to be submitted within the stipulated date and time as mentioned in the Bid document **as given in CRITICAL DATE SHEET.**
Bids shall be submitted online only at CPPP website: <https://eprocure.gov.in/eprocure/app> Bid documents may be scanned with 100 dpi with black and white option which helps in reducing size of the scanned document.
4. **Earnest Money Deposit:**
The Hard Copy of original instruments in respect of cost of earnest money must be delivered to the Superintending Archaeologist, Archaeological Survey of India, Guwahati on or before Bid opening date/time as mentioned in critical date sheet. Tenderer shall likely to be liable for legal action for non-submission of original payment instrument like DD etc. against the submitted Bid.
The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization, National Small Industries Corporation (NSIC) or Ministry of Culture.
5. **The EMD be submitted separately as under:**
 1. Tender inviting authority in the **Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle.**
 2. Time period for the execution of work/supply of materials shall be completed within **60 days** from the issue of the work order.
6. **Estimated Cost of Tender: ₹ 3,89,837/-** (Rupees Three lakh eighty nine thousand eight hundred and thirty seven only)

Address for communication, are as given below:-

Contact Details:

Contact Person	1. Shri K.Amarnath Ramakrishna, Superintending Archaeologist, 2. Shri S. K. Dutta, Asstt. Suptdg. Archl. Engineer.
Address for communication	Office of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, G.N.B.Road, Ambari, Guwahati – 781001 (Assam).

K.  03/09/18
अधीक्षण पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी सर्कल, गुवाहाटी-०१
Guwahati Circle, Guwahati-01

F. No. 2/14-W(C)/2018-19
Government of India
Office of the Superintending Archaeologist
Archaeological Survey of India
Guwahati Circle
G.N.B.Road, Ambari, Guwahati - 01

TENDER DOCUMENT (Financial Bid)

For the Work: **MW (Conservation) Annual Repair to David Scott's Memorial at Cherapunji, Meghalaya (2018-19)** as per detailed below.

Estimated Cost : 3,89,837/- (Rupees Three lakh eighty nine thousand eight hundred and thirty seven only)

READ TERMS AND CONDITION BEFORE FILLING UP THE SCHEDULE.SIGN ON ALL PAGES.

Open Tender for execution of complete work.

Item No.	Item Of Work	Quantity	Unit
1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m : All Kinds of Soil for FRB Cabin	26.46	Cum
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete	8.63	Cum
3	Providing and laying in position cement concrete of specified grade in 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering.	1.85	Cum
4	Random Rubble Masonry with hard stone including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size). Cement mortar in 1:6 (1 cement : 6 coarse sand)	15.91	Cum
5	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand)	72.91	Sqm
6	Provision of MS Chain (16 mm dia ring) with MS pipe 40 mm dia 2 mtr gaps MS Chain 46 Rmt MS Pipe – 20 Rmt	Whole work	
7	Painting with synthetic enamel paint of approve brand and manufacture to give an even shade : Two or more coats on new work	10.80	Sqm
8	Repairing of the existing damaged chain link around the monument including welding, replacing, painting, etc. wherever required.	Whole work	
9	Repairing and removing the black spray colour from the CNB and other board (Notice Board, direction board, etc.) and re-writing wherever required.	Whole work	
10	Engagement of labourer for cleaning and sweeping of site regularly	100	Unit

K. *[Signature]* 03/09/19
अधीक्षक पुरातत्त्वविद्
Superintending Archaeologist
भारतीय पुरातत्त्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwahati-01

