



प्रलकीर्तिमपावृणु

email/ Speed post

No. 2/37-W/2016-17

Government of India

Archaeological Survey of India

Guwahati Circle

Office of the Superintending Archaeologist

G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING LIMITED TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **27/02/2017** and the tender document will be received up to 14.30 hours on **28/02/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
Execution for replacement of roofing and showcase, installing fan, painting etc. at Archaeological Museum Sri Suryapahat, Goalpara	₹ 3,19,193/-	28/02/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 7,980/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the "Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1" including **Contractor's Registration certificate, PAN, VAT clearance certificate, Labour Registration, work order/experience certificate of similar works etc. (after completion of electrical work testing have to be done by any licensed supervisor)** failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.


Superintending Archaeologist

No. 2/37-W/2016-17-5122

Dated ... 14 FEB 2017

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The District Magistrate, Dist. Goalpara
3. The Executive Engineer, PWD, Dist. Goalpara
4. The Jr. Conservation Assistant, ASI, Camp office Suryapahar
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website "www.asi.nic.in".


For Superintending Archaeologist

- (1) Sale Price Rs. SL.No.
- (2) Name of Contractor.....
- (3) Date of Application for Tender form by Contractor.....
- (4) Date of receipt of Application in Circle/Branch Office.....
- (5) Date of issue of Tender papers.....
- (6) Date of receipt of Tender papers.....
- (7) Details of Cuttings, over-writings and erasings found on the tender at the time of opening it.....
- (8) Names and designations of Offices/Contractors present at the time of opening the Tender (a).....
- (b)

TENDER FOR EXECUTION OF WORK

14/11/17
 अधीक्षण पुरातत्वविद्
 Superintending Archaeologist
 भारतीय पुरातत्व सर्वेक्षण
 Archaeological Survey of India
 प्राङ्गण, गुवाहाटी-०१
 Circle, Guwahati-01
 Price of Tender- Rs. 500/-

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the time specified and the rates specified therein to the conditions of the contract for execution of work for replacement of roofing and showcase, installing fan, painting etc. at Sri Suryapahar Museum for 2016-2017

Memorandum

- | | |
|--|----------------------|
| 1. Earnest Money- Rs...7980/- | Demand Draft No..... |
| 2. Security deposit Rs...31,920/-. | Made up as bidder |
| 3. Estimated cost...3,19,193/- | |
| a) Payable immediately on the acceptance of tender
(including earnest money if deposited in cash with tender | ----- |
| b) Percentage to be deducted from bill | As admissible ----- |

Item No.	Sub-heads and Item of work	Quantity Or No.	Rate Rs.	Per	Amount Rs.
1/a	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of : G.S. Sheet.	31.08 sqm		sqm	
1/b	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m ²	31.08 sqm		sqm	
1/c	Supplying ,fitting,& fixing of the ceiling fan in the museum office building with transportation ,testing,& installing etc all complete. (ISI MARK)	2nos.		for whole item	
1/d	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever require:	1no		each	

1/e	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :One urinal basin with 5 litre white P.V.C. automatic flushing cistern.	1no		each	
1/f	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:.	1no		each	
1/g	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Circular shape 450 mm dia.	1no		each	
1/h	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 1.50 m nominal outer dia Pipes. 5.00m 2.25 nominal outer dia Pipes. 10.00m 3.40nominal outer dia Pipes. 10.00m 4.100mm nominal inner dia Pipes.5.00m 5.P.V.C. connection pipe 45 cm long.3nos 6Brass full way valve 50mm dia. 2nos 7Pillar cock (fancy) 15 mm foam flow.2nos 8C.P. Brass long nose bibcock 15 mm. 2Nos	Unit for whole item		Unit for whole item	
2/a	Provision for replacement of two showcases as previous type (size 0.65x0.40x2.55 & 2.46x0.40x2.55) and painting of heritage plaster on new showcases. 1.Water proof 90mm thick plaiy board. 20 sqm 2.Water proof 6mm thick plaiy board. 10 sqm 3.Sun maker 2 pic 4.Dendrite. 4lits 5.Fevical. 3lits 6.Nails 2'' . 3kg 7.Nails 1.5'' . 2kg 8.Nails 1'' . 2kg 9.Pin Nails' . 1kg 10.Plastic gutka 1 pkt 11.LED light & sock (1 wtt) 35 nos 12LED light & sock (3 wtt) 30 nos 13.Connecting wire 2 coil 14.Old showcase dismantling charge	2nos.			

	15.Fitting , fixing & making charge 16.Fitting the electric connection.				
	17.Liquid erklity putty. 3lits 18.Wood primer. 5 lits 19.Heritage plaster. 4 beg 20.C.M.C Medicine 1pkt 21.Borning. 2 gallon 22.Red oxide . 1.50 kg 23.4'' brash. 3 nos 24.Terpin oil , 4.5 lit			Unit for whole item	
2/b	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	472.20 sqm		sqm	
2/c	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	472.20 sqm.		sqm	
2/d	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)	472.20 sqm		sqm	
2/e	Provision for 1 no AC (1ton 3 star) Samsung with transportation, fitting & fixing charge.	1 no		each	
				Total	

(Rupees.....)

N.B. Quantity of work and materials may be increased/decreased at site

.....

Contractor's signature with seal

