



प्रत्नकीर्तिमपावृणु

email/ Speed post

No. 2/13-W(F)/2017-18

Government of India

Archaeological Survey of India

Guwahati Circle

Office of the Superintending Archaeologist

G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING LIMITED TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in works with Archaeological Survey of India for execution of work & supply of materials as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **09/08/2017** and the tender document will be received up to 14.30 hours on **10/08/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
OW (Plan) to Maintenance of Toilet Block at Ranghar Pavilion at Jaysagar, Sivasagar.	₹ 1,84,530/-	10/08/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 4,613/- only and cost of tender form of ₹500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, GST Registration No., Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

sdl/-
Superintending Archaeologist

No. 2/13-W(F)/2017-18 *1852*

Dated *01 AUG 2017*

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Sivasagar
3. The Executive Engineer, PWD, Dist. Sivasagar
4. The Sr. Conservation Assistant, ASI, Sivasagar Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
- ✓ 7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.

K. Atul
Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work OW (Plan) to Maintenance of Toilet Block at Ranghar Pavilion at Jaysagar, Sivasagar.

- Memorandum :-
- i) Earnest Money : ₹4,613/-
 - (ii) Security Deposit : ₹18,453/-
Estimated Cost : ₹1,84,530/-
 - a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
 - b) Percentage to be deducted from bill As admissible

Schedule of Quantities of work

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Method Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)	Remarks	
1. Engagement of Casual Sweeper for regular cleaning & Sweeping of Toilet Block and monument complex and also watch & ward duty at the site up to September 2017 to January 2018 as per Central Labour Commissioner Rate. (Payment will be made in three parts.)	Whole	Work at site	Work at site	Work to be completed by January, 2018		Whole Item		Tender items SL.No. 1 to 8 in Schedule is a single unit of Tender. No split up of items is entertained.	

Scale Price Rs. 500/-

Name of Contractor: **Sh. Mr. ...**

Date of Application for Tender form by Contractor:

Date of receipt of Application for Tender Branch Office:

Date of issue of Bill of Materials:

Date of award:

Details of cuttings and drawings figs.

on the tender at the time of opening the tenders.

Names and designations of Officers/Contractors present at the time of opening the tenders:

Date of opening of Tender : 10/08/2017

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster introducing disposal of rubbish to the dumping ground within 50 meters lead from the roof of existing store-shed.	29.44 Sq.M	-Do-	-Do-	Work to be completed by 30 days		Per SqM		Do
3	(a) Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone- III): 4 graded stone aggregate 12.5 mm nominal size). (b) Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification to the roof of existing store-shed.	29.44 Sq.M	-Do-	-Do-	-Do-		Per SqM		-Do-
4	Providing and fixing 35 mm thick factory made laminated veneer lumber door shutter conforming to IS: 14616 and TADS 15-2001 (Part B) including ISI marked M. S. pressed butt hinges bright finished of required size with necessary screws, all complete as per directions of Engineer-in-Charge an paneling with panels of :12 mm thick pre-laminated particle board (decorative lamination on both sides) grade -1, medium density flat pressed, three layer particle board FPT-1 or graded wood particle board FPT-1, conforming to IS: 3087, bonded with BWP type synthetic resin adhesive as per IS: 848 and pre-laminated conforming to IS: 12823. Grade-1, Type- II marked: for replacement of booking counter.	1.41 Sq.M	-Do-	-Do-	-Do-		Per SqM		-Do-



