



प्रत्यक्षीर्षिगपावृषु

No. 2/25-W/2015-16

Government of India

Archaeological Survey of India

Guwahati Circle

Office of the Superintending Archaeologist

G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING OPEN TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar civil works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **10 02.2017** and the tender document will be received up to 14.30 hours on **13/02/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
OW (Plan) to Thakurani Tilla at Paschim Pillak, Tripura (2015-16)	₹ 6,31,201/-	13/02/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 15,780/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the "Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1" including **Contractor's Registration certificate, PAN, VAT clearance certificate, Labour Registration, work order/experience certificate of similar works etc. (after completion of electrical work testing have to be done by any licensed supervisor)** failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

Superintending Archaeologist

No. 2/18-W(A)/2016-17-4789

Dated 31 JAN 2017

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The District Magistrate, Dist. South Tripura, Tripura, Belonia.
3. The Executive Engineer, PWD, Dist. South Tripura, Tripura, Belonia.
4. The Conservation Assistant, ASI, Udaipur Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website "www.asi.nic.in".

Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **OW (Plan) to Thakurani Tilla at Paschim Pillak, Tripura (2015-16)**.

Memorandum No. 11

- i) Earnest Money : ₹ 15,780/-
 (ii) Security Deposit : ₹ 63,120/-
 Estimated Cost : ₹ 6,31,201/-

- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
 b) Percentage to be deducted from bill As admissible

(Signature)
 31/11/17
 Superintending Archaeologist
 आर्कैोलॉजिकल सर्वेय ऑफ इंडिया
 भारतीय अन्वेषण, गुवाहाटी-01
 Archaeological Survey of India
 Indian Archaeological
 Circle, Guwahati-01

Schedule of Quantities of work

Demand Draft No. made up as under :
 1) Date Price Book
 2) Name of Contractor
 3) Date of Application for Tender form by Contractor
 4) Date of receipt of Application in Circle/Branch Office
 5) Date of issue of Tender Advertis
 6) Date of receipt of Tender bids
 7) Details of cuttings, over-writings and erasings found on the tender at the time of opening it
 8) Names and designations of Officers/Contractors, present at the time of opening the Tender :
 Date of opening of Tender : 13/02/2017

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
1	Providing and laying Vitrified tiles (0.60 x 0.60) in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08% and conforming to I.S.15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm thick bed of cement mortar 1:3(1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete.	121.00 sqm	Work site at Thakurani Tilla at Paschim Pillak, Tripura	Work site at Thakurani Tilla at Paschim Pillak, Tripura	Total works to be completed within 45 days	₹	Per sqm	₹	Tender items Sl.No.1 to 4 in Schedule is a single unit of Tender. No split up of items is entertained.
2	Providing and Fixing 15 mm thick densified regular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture spintone/cosmos / Hexa or equivalent of size 595 x 595 mm	88.00 sqm	Do	Do	Do	₹	Per sqm	₹	Do

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	<p>in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calcicum silicate ceiling tiles of approved texture (Spintone / Cosmos/hexa) in the grid, including cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required</p>								

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
3	<p>Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all T-sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by engineer-in-charge.</p> <p>Note :- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/opening (cut outs) having area less than 0.30 sqm. The calcium silicate ceiling tile shall have NRC value of 0.50 (Minimum), light reflection > 85%, non-combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity < 0.043 w/m 0 KC.</p> <p>Electrical Wiring : (a) Wiring for light/power plug with 2x4 sq.mm FR PVC insulated copper conductor single core cable in surface/recessed steel conduit along with 1 No. 4 sq.mm FR PVC insulated copper conductor single core cable for loop earthing as required</p>	50 mtrs.	Do	Do	Do		Per mtr		Do

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	(b) Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc. as required.	79 points	Do	Do	Do		Per point		Do
	(c) Supply & fixing following way prewired SP & N MCB distribution board of steel sheet for 240 volts. on surface/recess complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FR PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral link, earth bar, din bar, detachable gland plate, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).	1 No.	Do	Do	Do		Each		Do
4	Supplying, fitting and fixing of the Electrical items as per current market rates.		Do	Do	Do		Whole Item		Do
	a. LED Light b. Ceiling Fan c. Ceiling Rose d. Light for ceiling of Museum	12 Nos. 4 Nos. 48 Nos. 9 Nos.							

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	e. 8 Module G.I. Metal box	14 Nos.							
	f. 8 Module Platinum cone Plate	14 Nos.							
						Total			

NB: Quoting of Rates & Total cost in Col. No. 7 & 9 for all item is mandatory.

Rate should be quoted as analogous to PWD Schedule of Rates or CPWD DSR

(Rupees)

N.B. : Quantity of work and materials may be increased/decreased at site.

.....
Contractor's signature with seal.

Should this tender be accepted, I/we hereby agree to abide by and fulfill all the terms and provisions of the said conditions annexed hereto so far as applicable and/or in default thereof to forfeit and pay to the President of India or successor in office the sum of money mentioned in the said conditions. A sum of ₹ * is herewith forwarded in Cash/Treasury Challan as Earnest Money. If I/we fail to commence the work specified in the above memorandum or if I/we fail to deposit the amount of security deposit specified against (ii) (a) in the above memorandum in accordance with clause 1 of the said conditions of contract, I /we agree that the said President or his successors in office, without prejudice to any other right of remedy, shall be at liberty to forfeit the said earnest money absolutely, otherwise the said President or his successors in office shall also be at liberty to cancel the acceptance of the tender if I/we fail to deposit security amount as aforesaid.

.....
* Give particulars & number.

Signature
Full Address with PIN :

Signature of witness to signature of tenderer.

Full Address

Dated

The 2017

The above tender is hereby accepted by me on behalf of the President of India.

Dated

The 2017

Signature of the officer by whom the tender is accepted

TERMS & CONDITIONS

1. The works/supply shall be carried out by the Contractor/Firm strictly and in accordance with the ASI, Guwahati Circle's specifications and as per direction of Engineer-in-charge.
2. The rates given for the works should be inclusive of all taxes, leads and lifts, etc. Nothing extra shall be paid over the rates quoted by the contractor/firm.
3. **Rate should be quoted as analogous to PWD SR or CPWD DRS. As per CPWD manual and Archaeological Works Code the rate in excess of 5% with reference to overall estimate and 10% with reference to individual item are not acceptable.**
4. In case the material is not as per specification, the same shall be replaced by the contractor/firm with own cost. The department shall not be responsible for any theft or loss.
5. No payment shall be made to the contractor/firm if the materials are damaged due to natural calamities before measurement.
6. The tender must accompany the Earnest Money as stated in the tender form only and cost of tender form of ₹ 500/- only in the form of Bank Demand Draft/Pay Order of any Nationalized Bank in favour of Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati -1 payable at Guwahati.
7. It shall be the responsibility of the contractor/firm to ensure that no damage is caused to Govt. property at the site by his/their vehicle or labour party. Cost of such damages, if any, will be assessed at the discretion of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle and the same will have to be made good by the contractor/firm with own cost.
8. The tender submitted on behalf of a firm shall be signed by all the partners of the firm or by a partner who is duly authorized on behalf of the firm to enter into contract. Otherwise the tender is liable to be rejected.
9. **The firm/contractor must ensure the fulfillment of time line given by the office in the supply order/work order failing which the firm/contractor shall be debarred from further tender process in this office and the security deposit/earnest money shall be forfeited. The action pertaining to black listing the firm/contractor may also take place.**
10. All gold, silver, oil and other materials or any antiques and other similar things, which may be found, in or upon the site shall be the property of the Archaeological Survey of India. Contractor/firm shall deliver the same to such persons as the Department may from time to time appoint to receive the same.
11. Error/omission if any, shall be rectifiable with no claim.
12. No claim whatsoever on account of fluctuations in prices will be entertained.
13. If any litigation arises through labour court or labour commissioner & other court, etc. on account of litigation through labourers engaged by him, the contractor will be fully responsible. Moreover, if claim arises out of any litigation, the contractor will be responsible for payment of such claim.
14. The contractor/firm shall not be entitled to any compensation --whatsoever on account of any delay or default in the supply of materials mentioned in the schedule.
15. The Earnest money and security deposit of the successful contractor/firm will be forfeited, if he fails to comply with any of the conditions of the contract and work shall be carried out at risk and cost of the contractor/firm.
16. Overall rates shall be considered for approval of tender.

