



प्रलकीर्तिमपावृणु

No. 2/12-W(C)/2016-17

Government of India

Archaeological Survey of India

Guwahati Circle

Office of the Superintending Archaeologist

G.N.B.Road, Ambari, Guwahati – 1

email/Speed post

Dated, the

NOTICE INVITING TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar works with Archaeological Survey of India for execution of work & supply of materials as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **27/03/2017** and the tender document will be received up to 14.30 hours on **28/03/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

| Name of work | Estimated cost | Date of opening | Remarks |
|--|----------------|-------------------|--|
| O/W (P) to up gradation of Sub-Circle office at Sivasagar, Assam | ₹ 3,51,760/- | 28/03/2017 | Execution of work and supply of materials as per specification |

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 8,794/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

sd/-

Superintending Archaeologist

No. 2/21-W(H)/2016-17-5758

Dated22 MAR 2017

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Sivasagar
3. The Executive Engineer, PWD, Dist. Sivasagar
4. The Sr. Conservation Assistant, ASI, Sivasagar Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.

Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **QWSSB/2017/144/1** **Gradation of Sub Circle office at Sivasagar, Assam**

Memorandum :-

- i) Earnest Money : ₹ 8,794/-
- (ii) Security Deposit : ₹ 35,176/-
Estimated Cost : ₹ 3,51,760/-
- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill As admissible

Demand Draft No.
made up as under :

₹
₹
₹

Schedule of Quantities of work

| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) | (9) | (10) |
|----------|--|---|--------------------------------|---|--|--|---------|---|---|
| Item No. | Description or specification of work to be executed | Total Quantities of each to be executed | Places at which to be Executed | Quantities of work to be executed at each place | Dates by which execution at all places must be completed | Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹ | Unit | Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹ | Remarks |
| 1. | Dismantling old plaster/concrete or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. | 335.75 sqm | Work at site | Work at site | Work to be completed by 60 days | | Per SqM | | Tender items S.No. 1 to 25 in Schedule is a single unit of Tender. No split up of items is entertained. |

(Handwritten Signature)
 Asst. Superintending Archaeologist
 Archaeological Survey of India
 Circle, Guwahati-04

- (1) Name of Contractor.....
- (2) Date of Application for Tender form by Contractor.....
- (3) Date of receipt of Application in Circle/Branch Office.....
- (4) Date of issue of Tender notice.....
- (5) Date of receipt of single bids.....
- (6) Date of opening of bids.....
- (7) Details of cuttings, over-writings and erasings found on the tender at the time of opening bids.....
- (8) Names and designations of Officers/Contractors present at the time of opening the tender (a)..... (b).....
- Date of opening of Tender : 28/03/2017

| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) | (9) | (10) |
|-----|---|---------------|------|------|------|------|------------|-----|------|
| 2 | (a) Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size). (b) Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. Cement | 288.00 SqM | -Do- | -Do- | -Do- | -Do- | Per SqM | | Do |
| 3 | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge | 2.00 cum | -Do- | -Do- | -Do- | -Do- | Per CuM | | -Do- |
| 4 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below | 02 nos. | -Do- | -Do- | -Do- | -Do- | Per No | | -Do- |
| 5 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) | 3.48 cum | -Do- | -Do- | -Do- | -Do- | Per CuM | | -Do- |
| 6 | Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | 0.40 cum | -Do- | -Do- | -Do- | -Do- | Per CuM | | -Do- |

| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) | (9) | (10) |
|-----|---|-----------|------|------|------|------|---------|-----|------|
| 7 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bar. | 28 Kg | -Do- | -Do- | -Do- | -Do- | Per Kg | | -Do- |
| 8 | Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers | 3.15 Sqm | -Do- | -Do- | -Do- | -Do- | Per SqM | | -Do- |
| 9 | 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) | 36.00 Sqm | -Do- | -Do- | -Do- | -Do- | Per SqM | | -Do- |
| 10 | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc.,complete. Size of Tile 600x600 mm | 40.00 Sqm | -Do- | -Do- | -Do- | -Do- | Per SqM | | -Do- |
| 11 | Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make,in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. | 33.20 sqm | -Do- | -Do- | -Do- | -Do- | Per SqM | | -Do- |

