



प्रलकीर्तिमपावृणु

small/ Soeed post

No. 2/48-W/2017-18
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING LIMITED TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **14/09/2017** and the tender document will be received up to 14.30 hours on **15/09/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
OW to maintenance of Aizawl Circle Office (2017-18)	₹ 4,53,619/-	15/09/2017	Execution of work including supply of materials

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 11,341/- only and cost of tender form of ₹500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, GST Registration No., Labour registration, work order/experience certificate of similar works with ASI etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The Income Tax, Labour cess and other Taxes at prescribed rate will be deducted from the total billed amount at source during payment.



Superintending Archaeologist

No. 2/48-W/2017-18 - 2364

Dated ... 6/9/17

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Dy. Commissioner, Dist. Aizawl, Mizoram
2. The Executive Engineer, PWD, Dist. Aizawl, Mizoram
3. The Sr. Conservation Assistant, ASI, Aizawl Sub Circle.
4. Guwahati Circle Office Notice Board.
5. Website section of Guwahati Circle, Guwahati.
6. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.


Superintending Archaeologist

TENDER FOR EXECUTION OF WORK

Price of Tender ₹ 500/-

I/we hereby invite the item rate tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for **Execution of work on maintenance of Alzawl Circle Office**

Memorandum :-

- i) Earnest Money : ₹11,341/-
 (ii) Security Deposit : ₹45,362/-
 Estimated Cost : ₹4,53,620/-

Demand Draft No.
 made up as under :

- a) Payable immediately on the acceptance of tender
 (including earnest money if deposited in cash with tender)
 Percentage to be deducted from bill

As admissible

- ₹
 ₹
 (3) Date of Application for Tender form by Contractor.....
 (4) Date of receipt of Application in Circle/Branch Office.....
 (5) Date of issue of tender advertisement.....
 (6) Date of receipt of earnest money.....
 (7) Details of cuttings, over-writings and erasings found
 on the tender at the time of opening the.....

Schedule of Quantities of work

Names and designations of Officers/Contractors:
 present at the time of opening the Tender.....
 Date of opening of Tender : **15/09/2017**

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
1.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tabular sections/ appropriate Z section and other section of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically wherever required	160.61 Kgs	Work at site	Work at site	Work to be completed by 45 days		Per Kg.		Tender items SI.No. 1 to 7 in Schedule is a single unit of Tender. No split up of items is entertained.

	including cleat angle. Aluminium snap beading for glazing/paneling. C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)								
2.	Providing and fixing flat pressed 3 layer particle board medium density exterior grade (Grade-I) or graded wood particle board IS:3087 marked, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately): (12 mm thick)	110.55 Sqm	Work at site	Work at site	-do-		Per SqM		
3.	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade.	101.25 SqM	Work at site	Work at site	-do-		Per SqM		
4.	Providing and installation of AC (1.5 Ton) to guest room and S.A.	2 Nos	Work at site	Work at site	-do-		Per No		
5.	Providing and fixing veneer floor to the guest room.	78.50 SqM	Work at site	Work at site	-do-		Per SqM		
6	Provision for on toilet (2.50X2.80 m) made by wooden partition block (PVC) with fitting and fixing European Pan, wash basin water connection pipe etc and 30 cm base masonry work complete.	Whole	Work at site	Work at site	-do-		Whole		

