



प्रलकीर्तिमपावृणु

Small/ Speed post

No. 17/2 (Museum)2017-18-
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING LIMITED TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in works with Archaeological Survey of India for execution of work** (including supply of materials as per specification). The tender document will be issued on written request upto 05.00 hrs. on **14/09/2017** and the tender document will be received up to 14.30 hours on **15/09/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
Provision (MW) for fitting & fixing pipes of water connection, pvc water drums and replacement of worn water pump etc at Sri Suryapahar Museum complex , 2017-18Memorandum	₹ 2,84,217/-	15/09/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 7,105/- only and cost of tender form of ₹500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, GST Registration No., Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

- sd -
Superintending Archaeologist

No. 17/2 (Museum)2017-18- 2385 Dated 15/09/17

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Dy. Commissioner, Dist. Goalpara
2. The Executive Engineer, PWD, Dist. Goalpara
3. The Jr Conservation Assistant, ASI, Goalpara
4. Guwahati Circle Office Notice Board.
5. Website section of Guwahati Circle, Guwahati.
6. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.

Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **Provision (MW) for fitting & fixing pipes of water connection, pvc water drums and replacement of worn water pump etc at Sri Suryapahar Museum complex , 2017-18** Memorandum :

Handwritten signature and stamp:
 1. **Supervising Archaeologist**
 2. **Archaeological Survey of India**
 3. **राष्ट्रीय पुरातात्विक सर्वेक्षण**
 4. **पुरातात्विक सर्वेक्षण, गुवाहाटी-01**

- 1) Earnest Money : ₹7,105/-
- (ii) Security Deposit : ₹28,422/-
- Estimated Cost : ₹2,84,217/-
- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill As admissible

Schedule of Quantities of work

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)	Remarks
1.	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, filling, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.	15.09 cum	Work at site	Work at site	Work to be completed by 60 days		Whole Item		Tender items Sl.No. 1 to 10 in Schedule is a single unit of Tender. No split up of items is entertained.

- 12) Name of Contractor
- 13) Date of Application for Tender form by Contractor
- 14) Date of receipt of Application in Circle/Branch Office
- 15) Date of issue of tender details
- 16) Date of receipt of tender details
- 17) Details of cuttings, over writings and erasings found on the tender at the time of opening thereof
- 18) Names and designations of Officers/Contractors, present at the time of opening the Tender
- 19) Date of opening of Tender : 15/09/2017

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	1.42 cum	-Do-	-Do-	Do-		Whole Item		Do
3	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	2.54 cum	-Do-	-Do-	-Do-		Whole Item		-Do-
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints, T & I-how socket etc complete as per direction of Engineer in Charge.)	Whole work	-Do-	-Do-	-Do-		Per Mt.		-Do-
5	Provision for PVC water tanks/ drums (1000 lit.) with top cover for drinking water purpose in Museum complex with fitting & fixing, transportation, proper water connection, testing, with other necessary accessories etc all complete as per direction of engineer in-charge.	4nos							

