



email/ Speed post

No. 2/26-W/2015-16
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING OPEN TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar civil works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 17.00 hrs. on **20/02/2017** and the tender document will be received up to 14.30 hours on **21/02/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.


Name of work	Estimated cost	Date of opening	Remarks
SR (Plan) to Rock-cut Sculpture at Unakoti (2015-16)	₹ 22,92,054/-	21/02/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 57,301/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including **Contractor’s Registration certificate, PAN, VAT clearance certificate, Labour Registration, work order/experience certificate of similar works etc. (after completion of electrical work testing have to be done by any licensed supervisor)** failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.



Superintending Archaeologist

No. 2/22-W(D)/2015-16 

Dated **9 FEB 2017**

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The District Magistrate, Dist. Unakoti, Tripura
3. The Executive Engineer, PWD, Dist. Unakoti, Tripura
4. The Conservation Assistant, ASI, Udaipur Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.


Superintending Archaeologist

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
4	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete.	1936.41 Kg.	Do	Do	Do		Per Kg.		Do
5	Centering & Shuttering including strutting propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform.	120.00 SqM	Do	Do	Do		Per SqM.		Do
6	Demolishing R.C.C. work manually by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge	0.33 CuM	Do	Do	Do		Per CuM		Do
7	Demolishing brick work manually by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge in cement mortar	1.36 CuM	Do	Do	Do		Per CuM		Do
8	Half Brick Masonry with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in foundations and plinth in cement mortar 1:4 (1 cement : 4 coarse sand)	15.00 CuM	Do	Do	Do		Per CuM		Do
9	20mm cement plaster inner and outer surface of the building in c.m. 1:4	129.00 SqM	Do	Do	Do		Per SqM		Do
10	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. out side and inside	129.00 SqM	Do	Do	Do		Per SqM		Do
11(a)	Finishing walls with water proofing cement paint of required shade. New work (Two or more coats applied @ 3.84 kg./10 SqM.)	34.00 SqM	Do	Do	Do		Per SqM		Do
11(b)	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade	95.00 SqM	Do	Do	Do		Per SqM		Do

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
12	Painting steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ .090 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	46.75 SqM	Do	Do	Do		Per SqM		Do
13	Providing and fixing M.S. grill of required pattern in frames of windows etc. with M.S. glats, square or round bars etc including priming coat with approved steel primer all complete	124.00 Kg.	Do	Do	Do		Per Kg.		Do
14	Engaging labour for shifting and proper placing of sculpture by the ordinary labour	60 Nos.	Do	Do	Do		Per No		Do
15	Earth work in excavation for construction of ticket room footing tie beam etc.	9.10 CuM	Do	Do	Do		Per CuM		Do
16	Providing P.C.C. (1:2:4) for base of Toilet and reception centre wall and column etc.	1.90 CuM	Do	Do	Do		Per CuM		Do
17	Flat brick soiling	11.85 SqM	Do	Do	Do		Per SqM		Do
18	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement.	4.19 CuM	Do	Do	Do		Per CuM		Do
19	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete	341.87 Kg.	Do	Do	Do		Per Kg.		Do
20	Centering & shuttering including strutting propping etc. and removal of form for suspended floors, roofs, landing, balconies and access platform.	38.60 SqM	Do	Do	Do		Per SqM		Do
21	Brick work in foundation & plinth with common brunt clay modular bricks of class designation 7.50 in foundation and plinth in cement mortar 1 : 4 (1 cement : 4 coarse sand)	3.48 CuM	Do	Do	Do		Per CuM		Do

