



No. 2/9-W(R)/2015-16
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING OPEN TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar works with Archaeological Survey of India for execution of work by providing Labours & supply of materials as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **01/08/2017** and the tender document will be received up to 14.30 hours on **02/08/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
SR to Karenghar Palace at Jaysagar (2015-16)	₹ 8,24,326/-	02/08/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 20,608/- only and cost of tender form of ₹500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, GST Registration No., Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

No. 2/9-W(R)/2015-16

1554

Dated

21 JUL 2017

Superintending Archaeologist

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Sivasagar
3. The Executive Engineer, PWD, Dist. Sivasagar
4. The Sr. Conservation Assistant, ASI, Sivasagar Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
- ✓ 7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.

Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby invite the item rate tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work SR to Karengnar Palace at

Jaysagar (2015-16)

Memorandum :-

- i) Earnest Money : ₹20,608/-
- (ii) Security Deposit : ₹82,433/-
Estimated Cost : ₹8,24,326/-
- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill

Demand Draft No.
made up as under :

- 1) Sale Price Rs.
- 12) Name of Contractor.....
- 13) Date of Application for Tender form by Contractor.....
- 14) Date of receipt of Application in Circle/Branch Office.....
- 15) Date of issue of tender order.....
- 16) Date of receipt of tender order.....
- 17) Details of cuttings, over-writings and erasings found on the tender at the time of opening the same.....
- 18) Names and designations of Offices/Contractors present at the time of opening the tender.....
- 19) Date of opening of Tender.....

Schedule of Quantities of work

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Item/Description or specification	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)	Remarks	
1. Provision for centering, shuttering and scaffolding for restoration of traditional ancient chala-roof etc. measuring about 34.40 SqM		Whole	Work at site	Work at site	Work to be completed by 90 days		Whole		Tender items Sl.No. 1 to 11 in Schedule is a single unit of Tender. No split up of items is entertained.

K. Arakambin
अरकंभिन
Supervising Archaeologist
Archaeological Survey of India
आर्कैलॉजिकल सर्वे ऑफ इंडिया
Guwahati Circle, Guwahati-781001

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
2	Provision for cleaning of excavated area for conservation.	194.00 Sqm	-Do-	-Do-	-Do-		Per SqM		Do
3	Restoration of traditional ancient <i>chala-roof</i> of the top floor with special size brick (25 cm x 17 cm x 4 cm) and Lime-surkhi-sand (1:1:1) mortar with organic materials such as Molases, Bet Fruit Gum, Gul Nut, Mehi, Polymar Latex etc.	49.89 CuM	-Do-	-Do-	-Do-		Per CuM		-Do-
4	Provision for Lime concrete (1:2:4) mixing with organic materials including beating up to 7 days to the floor of excavated area and restored structure of roof.	14.22 CuM	-Do-	-Do-	-Do-		Per CuM		-Do-
5	Provision for lime surkhi sand (1:1:1) plaster mixing with organic materials to the both side of restored roof (30 mm thick in two coats).	125.00 SqM	-Do-	-Do-	-Do-		Per SqM		-Do-
6	Pointing & Filletting to the walls of excavated area with lime mortar (1:1:1) mixing with organic materials.	165.00 SqM	-Do-	-Do-	-Do-		Per SqM		-Do-
7	Provision for unskilled labour for lead and lift of materials from Road side stock to work side {Special size brick= 26,100 nos. (appx), unslaked lime=6336 kg. (appx), River sand=7.56 CuM, brick surkhi= 13.65 CuM (appx), brick aggregate (20 mm) = 16.00 CuM (appx)}	Whole work	-Do-	-Do-	-Do-		Whole work		-Do-
8	Provision for unskilled labour for cleaning of site during and after completion of works. Total Area 500 Sq. Meter (Appx)	Whole work	-Do-	-Do-	-Do-		Whole work		-Do-

