



प्रत्नकीर्तिमपावृणु

No. 2/14-W(A)/17-18-
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING LIMITED TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having one years experience in works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **03/08/2017** and the tender document will be received up to 14.30 hours on **04/08/2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
SR to U-Maw-Dur-Briew at Nartiang, Jowai, Meghalaya (2017-18)	₹ 13,43,642/-	04/08/2017	Execution of work including supply of materials

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 33,591/- only and cost of tender form of ₹500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the "Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1" including Contractor's Registration certificate, PAN, VAT clearance certificate, GST Registration No., Labour registration, work order/experience certificate of similar works with ASI etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The Income Tax, Labour cess and other Taxes at prescribed rate will be deducted from the total billed amount at source during payment.



Superintending Archaeologist

No. 2/14-W(A)/17-18- 1641

Dated 25 JUL 2017

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Jaintia Hills
3. The Executive Engineer, PWD, Dist. Jaintia Hills
4. The Sr. Conservation Assistant, ASI, Guwahati Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website "www.asi.nic.in".


Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby invite the item rate tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work SR to U-May-Dur-Briew at Nartiang, Jowai, Meghalaya (2017-18)

Memorandum :-

- i) Earnest Money : ₹33,591/-
- (ii) Security Deposit : ₹1,34,364/-
Estimated Cost : ₹13,43,642/-
- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill As admissible

Demand Draft No.
made up as under :

- (1) Name of Contractor.....
- (2) Date of Application for Tender form by Contractor.....
- (3) Date of receipt of Application in Circle/Branch Office.....
- (4) Sale Price Rs.....
- (5) Date of issue of tender order.....
- (6) Date of receipt of tender order.....
- (7) Details of currency, over-writings and erasings found on the tender at the time of opening the.....
- (8) Names and designations of Officers/Contractors, present at the time of opening the Tender.....
- (9) Date of opening of Tender : 04/08/2017

X. Anil Kumar
Archaeologist
Superintending Archaeologist
Archaeological Survey of India
Guwahati Circle

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Description of specification No. of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks	
1. Supplying and filling in plinth with locally available earth for parking area including watering, ramming, consolidating and dressing complete.	314.60 cum	Work at site	Work at site	Work to be completed by 180 days		Per CuM		Tender items Sl.No. 1 to 7 in Schedule is a single unit of Tender. No split up of items is entertained.	

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
2.	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete.	462.25 sqm	Work at site	Work at site	-do-		Per SqM		
3.	Supplying and stacking of stone aggregate of 63 mm to 45 mm size stone aggregate at site.	69.34 cum	Work at site	Work at site	-do-		Per CuM		
4.	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.	69.34cum	Work at site	Work at site	-do-		Per CuM		
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	69.74 cum	Work at site	Work at site	-do-		Per CuM		
6	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m :All kinds of soil.	3.40 cum	Work at site	Work at site	-do-		Per CuM		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars.	111.00 kg	Work at site	Work at site	-do-		Per Kg		



