OPEN TENDER NOTICE

For MW (Cons) for SR to Bordol Temple at Biwanathghat, Tezpur (2018-19)

REFERENCE NO. E. NO: 2/28-W(A)/2018-12 - 35-2 75-2 75-23



GOVERNMENT OF INDIA MINISTRY OF CULTURE ARCHAEOLOGICAL SURVEY OF INDIA GUWAHATI CIRCLE, GUWAHATI

> अधीक्षण पुरातन्त्र्यावव् Superintending Archaeologist पारतीय पुरातन्त्र सर्वेक्षण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी ०१ Guwahati Circle, Guwahati-01

Section-1 Table - A: Time and Work Frame

FOR EXECUTION OF WORK - MW (Cons) for SR to Bordol Temple at Biwanathghat, Tezpur (2018-19)

Manual bids shall not be accepted

CRITICAL DATE SHEET

1.	Date of issue of Tender	23.01.2019 at 17.30 Hrs.
2.	Bid Document Download/Sale Start	24.01.2019 from 10:00 Hrs.
	Date	
		27.4
3.	Date of Pre Bid Conference For	N.A.
	clarifying issues and doubts, if any,	
	about specification of material and	
A Company	services projected in Bid document.	
4.	Start date for submission of filled-in	24.01.2019 from 10.30 Hrs.
	tender document.	
5.	Bid Submission End Date	02.02.2019 up to 12.00 Hrs.
٦.	Did Subilitssion End Date	
6.	Date of opening of Technical/Financial	04.02.2019 at 12.05 Hrs.
	bid	
		NIA
7.	Date of meeting with Bidders post	N.A
	Technical Bid opening for presentation	
	and Document Verification	
		120 Davis
8.	Validity of Bid	120 Days.
1		

अधीक्षण प्रातन्त्रीवव् Superintending Archaeologist भारतीय प्रातन्त्र सर्वेक्षण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी-०१ Guwahati Circle, Guwahati-01 Dear Sir,

The Archaeological Survey of India invites online Bids in the prescribed form under the Two Bid system i.e. Technical Bid and Financial Bid for the Execution of work: — MW (Cons) for SR to Bordol Temple at Biwanathghat, Tezpur (2018-19)

The system of e-tendering shall be adopted, comprising of Technical Bid and the Financial Bid.
 Document Download: Tender documents may be downloaded from CPPP site https://eprocure.gov.in/eprocure/app and www.asiguwahaticircle.gov.in as per the schedule as given in CRITICAL DATE SHEET.

Technical Bid should, inter alia, contain all technical details of services and solutions to be provided along with such documentary proofs. Financial Bid should, inter alia, indicate item-wise price and other commercial/financial terms against the items mentioned in the Technical Bid.

2. Bid Submission:

Applicants/intending or interested Bidders are invited to submit their proposal after carefully reading the Request for Proposal (RFP) by providing (a) Technical Bid, and (b) Financial Bid, separately, clearly mentioning (i) 'Technical Proposal', and (ii) 'Financial Proposal' respectively. Such proposals are to be submitted within the stipulated date and time as mentioned in the Bid document as given in CRITICAL DATE SHEET.

Bids shall be submitted online only at CPPP website: https://eprocure.gov.in/eprocure/appBid documents may be scanned with 100 dpi with black and white option which helps in reducing size of the scanned document.

3. Earnest Money Deposit:

The Hard Copy of original instruments in respect of cost of earnest money must be delivered to the Superintending Archaeologist, Archaeological Survey of India, Guwahati on or before Bid opening date/time as mentioned in critical date sheet. Tenderer shall likely to be liable for legal action for non-submission of original payment instrument like DD etc. against the submitted Bid.

The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization, National Small Industries Corporation (NSIC) or Ministry of Culture.

4. The EMD be submitted separately as under:

- Tender inviting authority in the <u>Superintending Archaeologist</u>, <u>Archaeological Survey of India</u>, <u>Guwahati Circle</u>.
- 2. Time period for the execution of work/supply of materials shall be completed within 120 days from the issue of the work order.
- Estimated Cost of Tender: ₹ 14,42,469/- (Rupees Fourteen lakh Forty Two thousand Four hundred and Sixty Nine only)

Address for communication, are as given below:-

Contact Details:

Contact Person

1. Shri K.Amarnath Ramakrishna, Superintending Archaeologist.
2. Shri S. K. Dutta, Dy. Suptdg. Archaeological Engineer.

Office of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, 5th Floor, West End Block, HOUSEFED Complex Beltola -Basistha Road, Guwahati -781006

अधीक्षण प्रानन्तविद् Superintending Archaeologist बारतीय प्रातस्य सर्वेक्षण Archaeological Survey of India गुवारों मण्डल, गुवारों-०१ Guwahati Circle, Guwahati. F. No. 2/28-W(A)/208-19
Government of India
Office of the Superintending Archaeologist
Archaeological Survey of India
Guwahati Circle
5th Floor, West End Block, HOUSEFED Complex
Beltola -Basistha Road, Guwahati -781006

TENDER DOCUMENT (Financial Bid)

For the Work: MW (Cons) for SR to Bordol Temple at Biwanathghat, Tezpur (2018-19)

Estimated Cost : ₹ 14,42,469/- (Rupees Fourteen lakh Forty Two thousand Four hundred and Sixty Nine only)

READ TERMS AND CONDITION BEFORE FILLING UP THE SCHEDULE.SIGN ON ALL PAGES. Open Tender for execution of complete work,

ltem	Item Of Work	Quantity	Unit
No.	Provision for restoration of damaged brick apron with 60% old and 40% new brick in proportion 1:1:1 Pointing over the brick apron on all sides with composite mortar 1:1:1 Provision for 25 mm to 30 mm thick Lime-Sand- Surkhi Plaster (1:1:1)in two coats mixing with organic materials to the walls and roof of the monument after removal of old dead plastering including raching the joints and cleaning, washing etc and preparing the surface for replastering.		Cum
2			Sqm
3			Sqm
4	Renewing lime concrete in (1:1:1) of lime, surkhi and brick aggregate mixing with organic materials including beating upto 7 days to the floor and roof after removal of old damaged decomposed and deteriorated lime concrete/rubbish etc	0.95	Cum
5	Provision for stitching of cracks of the monument after cleaning, brushing & washing of the crakes.		Rmt
6	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.		Cum
7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar		Cum
8	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	113.21	Kg
9	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m: All kinds of soil	28.85	Cum

अधाक्षण प्रातन्वविद् Superintending Archaeologist भारतीय प्रातन्व सर्वक्षण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी-०१ Guwahati Circle, Guwahati-01

2. All kinds of soil 2. Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete. 2. The price on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks. 2. Centering and shuttering including strutting, propping etc. and removal of form work for: Columns, piers, abutments, pillars, posts and struts 3. Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 3. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 3. Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 4. Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 4. Providing and Robert of the structure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 4. Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel lusts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 4. Provision
ramming, consolidating and dressing complete. 11 Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks. 12 Centering and shuttering including strutting, propping etc. and removal of form work for: Columns, piers, abutments, pillars, posts and struts 13 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand) (20ne-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of requir
ramming, consolidating and dressing complete. 11 Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks. 12 Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts 13 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (2 none-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/
designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks. 12 Centering and shuttering including strutting, propping etc. and removal of form work for: Columns, piers, abutments, pillars, posts and struts 13 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineerincharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Pinishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers
with sand, with common burnt clay non modular bricks. 12 Centering and shuttering including strutting, propping etc. and removal of form work for: Columns, piers, abutments, pillars, posts and struts 13 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering: -All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying \$&\$ Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, I/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint t
12 Centering and shuttering including strutting, propping etc. and removal of form work for: Columns, piers, abutments, pillars, posts and struts 13 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
of form work for: Columns, piers, abutments, pillars, posts and struts Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of pri
of form work for : Columns, piers, abutments, pillars, posts and struts Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329 : 150 mm dia Ductile Iron Class K-7 pipes Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement: 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Provision for fixing of radium signage on steel plate 20 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
and applying a priming coat of approved steel primer all complete. 14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 Finishing with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
14 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). 6.54 Cumm nominal size). 6 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-7 pipes 6 Rr conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-7 pipes 6 Rr designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) 9.2 Cumm all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) 7 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 5.4 Sq Sq 20 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) 414.85 Sq 212.35 Sq 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.90 ltr/10
excluding the cost of centering and shuttering - All work up to plinth level: "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, I/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineerincharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
: "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
12:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-7 pipes 16
mm nominal size). 15 Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes 16 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 212.35 Sq Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
conforming to IS: 8329: 150 mm dia Ductile Iron Class K-7 pipes Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Provision for fixing of radium signage on steel plate This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of mix: 1:6 (1 cement: 6 fine sand) This initial matter of
designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) 17 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand) Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 22.35 Sq. 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 5.4 Sq. 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 212.35 Sq. 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 21 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 212.35 Sqi 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
fasteners etc.). 18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
18 Provision for fixing of radium signage on steel plate 19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
19 20 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 20 Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm) Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
Work (Two or more coats applied @ 3.84 kg/10 sqm) 21 Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @
0.80 ltr/10 sqm of approved brand and manufacture
Providing and laying gang saw cut 18 mm thick, mirror polished pre
molded and pre polished machine cut granite stone of required size and
shape of approved shade, colour and texture in footpath, flooring in road
side plazas and similar locations, laid over 20mm thick base of cement 2.16 Sq.
mortar 1:4 (Icement : 4 coarse sand) including grouting the joints with
white cement mixed with matching pigment, epoxy touch ups etc.
complete as per direction of Engineer-in-Charge. With granite stone of
area less than 0.50 sqm 23 Provision for engraving charges on stone plate for CNB 2.16 Sq
5 5 5
24 Provision for repairing the existing water cooler for visitors drinking For
facility. Details- (a) Motor binding - 1 pc (b) repair of starter- 1 pc © whole
Cable wire (1" dia) - 10 mtr including service charge and tax etc. job
25 Provision for supplying fitting and fixing of 1 no. R.O. system and 1 no.
syntex tank along with plumbing works etc. for drinking facilities of whole

अधीक्षण प्रातस्त्विद्
Superintending Archaeologist
भारतीय प्रातस्त्व सर्वेक्षण
Archaeological Survey of India
प्राह्मी मण्डल, ग्वाह्मटो-०१
Guwahati Circle, Guwahati-01

	visitors. Details- (a) Sintex Tank (1000 ltr) - 1 no. (b) R.O. water system (8 ltr) ISO/ISI marked - 1 pc (c) CPVC pipe (25 mm) - 30' (d) CPVC pipe (12.5mm) - 15' (e) Neeple (6 pc), Taps (4 nos.), Socket (15 pc) including plumbing charges and tax etc.	job	
26	Provision for repairing and painting the existing MS Water Tank (1.50 x 1.50 x 4.90) and shifting the water cooler from temple to inside it.	For whole job	
27	Provision for renewing and repairing the electrical lines of Bordol Temple. Details- (a) Cable wire (12.5 mm dia) - 15 mtr, (b) Copper wire (1.5 mm dia) = 30 mtr (c) Main Switch (15 amp) - 2 pc (d) 8 module box with plate - 2 nos, (e) 3 module box with plate - 2 nos, (f) 16 amp switch and socket - 1 set, (g) 6 amp switch - 8 nos., 6 amp socket - 2 nos. including electrical charges and taxes etc.	For whole job	
28		For whole job	

TENDER NOTICE

Online E-Tender on behalf of the President of India, are invited under <u>Two Bid System</u> i.e. Technical Bid and Financial Bid from reputed, experienced and financially sound contractors/suppliers/Firms/Agencies who have past experience in conservation works with Archaeological Survey of India for at least <u>Two years</u> for the work of MW (Cons) for SR to Bordol Temple at Biwanathghat, Tezpur (2018-19)

- 1. The time period for execution of the work is 120 days from the date of issue of work order.
- 1. Complete Tender Document can be downloaded from the website of CPPP & of this Department (https://eprocure.gov.in/eprocure/app and www.asiguwahaticircle.gov.in).
- 2. Interested contractors/suppliers/Firms/Agencies may submit their online proposal complete in all respects within the stipulated date and time as mentioned in the Tender documents as given in CRITICAL DATE SHEET. <u>Bids shall be submitted online only at CPPP website https://eprocure.gov.in/eprocure/app.</u>
- 3. Two Nos of separate D.D. (Nationalized Bank) (issued after publication of NIT) as the (i) Earnest Money Deposit (EMD) ₹ 36062/-(Rupees Thirty Six thousand and Sixty Two only) & (ii) Tender cost (Non-refundable) ₹ 500/- (Rupees five hundred only) in favour of "Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati" to be submitted to the Office of Superintending Archaeologist, Archaeologist, Archaeological Survey of India, Guwahati Circle, 5th floor, West End Block, HOUSEFED Complex, Beltola-Basistha Road Guwhahati-781006 prior to the opening date of the tender. The bid without EMD & Tender cost will be rejected summarily.
- 4. No tender shall be entertained after the deadline under any circumstances what so ever. The Technical Bid of tender will be opened on 04/02/2019 at 12.05 hrs.
- 5. This ASI reserves the right to amend or withdraw any of the terms and conditions contained in the Tender Document or to reject any or all tenders without giving any notice or assigning any reason. The decision of the Superintending Archaeologist, ASI, Guwahati Circle in this regard shall be final and binding on all parties in all circumstances.

Superintending Archaeologist Archaeological Survey of India, (Tawahati direke For and on behalf of the Presidented India

Copy to:

1. OFFICE NOTICE BOARD, A.S.I., Guwahati Circle, Guwahati - 6

2. The Web Manager, A.S.I., 24, Tilak Marg, New Delhi - 1.

Office Copy.

अधिकण पुरातस्वविद्
Superintending Archaeologist
गारतीय पुरातस्व सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwahati-01

SCOPE OF WORK AND GENERAL INSTRUCTIONS FOR TENDERERS

The Superintending Archaeologist, ASI, Guwahati Circle, Guwahati requires online E-Tenders from reputed, well established and financially sound Contractors/Suppliers/Firms/Agencies who have past experience in conservation works with Archaeological Survey of India at least 2 (Two) years for the work of MW (Cons) for SR to Devidol at Jaysagar, Sivasagar, Assam (2018-19)

- 1. The tendering Contractors/Suppliers/Firms/Agencies are required to enclose photocopies of the following documents along with the Technical Bid, failing which their bids shall be summarily/ out-rightly rejected and will not be considered any further:-
 - (a) Copies of the valid Registration Certificate.
 - (b) Copy of PAN/GIR/TIN card No.
 - (c) Copy of IT return filed for the last three financial years along with Proof of annual turnover of the firm for the last 3 years ending on 31/03/2018.
 - (d) Copies of the Service Tax/Sales Tax/GST registration certificate along with latest Service tax/Sales Tax clearance certificate.
 - (e) Declaration regarding black listing as per format attached.
 - (f) Experience certificate of having successfully completed similar works (as mentioned above) of <u>2</u> <u>vears</u> ending last financial year.
- 2. The rate for complete work should be quoted in figures and words including GST and other Taxes/charges as applicable.
- 3. The Contractors/Suppliers/Firms/Agencies will be permitted to attend at the time of tender opening.
- 4. If the date of opening of the tender happens to be a holiday, the tender will be opened on the next working day.
- 5. The right of acceptance of a tender will with the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle who does not bind himself/herself to accept the lower tender and reserves to himself/herself the authority to reject any or all the tenders without assigning any reason. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- 6. Contractor should visit the working site prior to rate tendering as well as have to furnish certificates thereof in written along with the tender.
- 7. The work to be executed and deduction of voids will be as per CPWD specifications, IS code and as per Archaeological Survey of India specification.
- 8. Water arrangement/Scaffolding/T&P articles will be managed by the contractor.
- 9. The quantity/item of work can be increased / decreased as per site requirements.
- 10. Before execution of work contractor must sign the agreement in this office.
- 11. The materials pertaining to this work should be checked by the competent officer.
- 12. Security Deposit 10% of 1st 1,00,000/-

7.5% of 2^{nd} 1,00,000/-

5% of remaining balance amount of tender cost.

13. The ASI reserves the right to amend or withdraw any of the terms and conditions contained in the Tender Documents or to reject any or all tenders without giving any notice or assigning any reason.

> Superintending Archaeologist भारतीय पुरातस्य सर्वेक्षण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी-०१ Şuwahati Circle, Guwahati-01

The decision of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati in this regard shall be final and binding on all parties in all circumstances.

- 14. Conditional bids shall not be considered and will be out rightly rejected in the very first instance.
- 15. Contractor will be responsible for timely payment to the supplier/labour and statutory authorities and compliance of all statutory provisions relating to minimum wages/specified contract amount etc. in respect of the person deployed by him in the work.
- 16. The Contractor shall also be liable for depositing all tax, levies, cess etc on amount of work done/ supply of materials/ service rendered by him to the ASI to the concerned tax collection authorities from time to time as per extant rules and regulations on the matter.
- 17. Whenever the rates quoted by the contractor in figures and in words tally but the amount is not worked out correctly, the rate quoted by the contractor will be taken as correct and not the amount.
- 18. The total cost quoted by the bidders shall be worked out for deciding the lowest bidder for acceptance of tender.
- 19. The rate quoted should include all taxes etc. ASI will not entertain any claim whatsoever in this regard.
- 20. In case contractor's signature on tender is fixed in an Indian Language, the rate/ amount/ percentage above or below should also be written in the same language. In the case of illiterate contractors the rates/percentage should be attested by a witness.
- 21. The discretion of acceptance of tender, will rest with the Circle/Branch Officer/Regional Director/Director General, A.S.I who does not bind himself to accept the lowest tender and reserve to himself the authority to reject any or all of the tenders received, without the assigning any reason. Any tender, in which any of the prescribed conditions are not fulfilled or are incomplete in any respect is liable to be rejected.
- 22. The contractor shall not be permitted to tender for works in the Archaeological Survey of India, Circle/Branch Office (Responsible for award and execution of contracts) in which his near relative is posted as an officer in any capacity.
- 23. No. Engineer of Gazetted rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of two years of his retirement from Government service, without the prior permission of the Government of India as aforesaid before submission of the tender or engagement in the contractor's service.
- 24. The tender of the work shall not be witnessed by a contractor or contractors who himself/themselves/has/have tendered or who may tender for the same work.

EVALUTION CRITERIA:

- The bidder who fulfills Technical Eligibility Requirement mentioned under Technical Eligibility Requirement shall be declared technically qualified and financial bid in respect of only technically qualified bidder shall be opened.
- 2. The bidder who quotes lowest rates for the work in financial bid will be declared L1.
- In case of tie in lowest rate, the Contractors/Suppliers/Firms/Agencies who have completed
 more work orders in last 2 years shall be declared L1. Copies of Work Order and
 completion certificate from employer shall be provided along with Technical Bid.
- 4. The work shall be awarded to L1 bidder.

Superintending Archaeologist
Archaeological Survey of India, Duwaling Orcle
For and on behalf of the President of India
author quantities
Superintending Archaeologist
within quantities
Archaeological Survey of India
quantities
quantities
quantities
Guwahati Circle, Guwahati-01

TECHNICAL ELIGIBILITYREQUIREMENT FOR THE TENDERING CONTRACTORS/ SUPPLIERS/FIRMS/AGENCIES (Technical Bid)

The tendering Contractors/Suppliers/Firms/Agencies should fulfill the following **ELIGIBILITY** requirement and furnish the same with self attested copies of documents with technical bid.

SI No	REQUIREMENT	COPY OF RELAVANT DOCUMENT	ENCLOSED YES/NO.	PAGE NO. OF BID DOCUMENT
1	Contractors should be registered with the appropriate registration authority.	Copy of Registration Certificate issued by CPWD/PWD		
2	Copy of PAN/GIR/TIN card No.	Copy of PAN/GIR /TIN No.		
3	TT returns / Annual turnover for the last 3 FY years	Copy of IT returns of last 3 years along with certificate of annual turnover of last 3 years from Statutory Auditor/authority		
4	Contractors should be registered with GST and Labour Act.	Copy of registration certificates along with latest GST		
5	Contractors should have registered with EPF/	Copy of EPF / ESI Registration certificate		
6	Declaration regarding black listing as per	Declaration in enclosed format.		
7	Contractors should have past experience in similar works with ASI for <u>02 years</u> .	Copy of the Work Order/completion certificates.		

(Signature of the Bidder, with official Seal)

DECLARATION

. •	this declaration and
	this declarat

- 2. I have carefully read and understood all the terms and conditions of the tender and undertake to abide by them.
- 3. My agency/firm has not been blacklisted/debarred from participating in tender of any Ministry/ Department of Government of India and Government of India undertaking in the last Three (3) years as on date of opening of this Tender.
- The information/ documents furnished along with the above application are true and authentic to the best of my knowledge and belief.
- I/We am/are well aware of the fact that furnishing of any false information/fabricated document would lead to rejection of my tender at any stage besides liabilities towards prosecution under appropriate law.

Signature of Authorized person(s)

Date:

Full Name:

Place:

Seal:

अधीकाण प्रातास्त्रीवर् Superintending Archaeologist भारतीय प्रातास सर्वकाण Archaeological Survey of India गुवाली मण्डल, गुवाली-वर् Guwakath Girela Guwahati-01

DECLARATION

- Give particulars & number:
- Signature of Tenderer:
- Address with TIN & GST No:
- Signature of Witness:
- Address:
- Date:

The above tender is hereby accepted by me on behalf of the President of India.

Signature of the officer by whom
tender slaccepted.
अधारण प्रातन्त्रविद्
Superintending Archaeologist
भारतीय प्रातन्त्र सर्वेक्षण
Archaeological Survey of India
गुवाहाटी मण्डल, गुवाहाटी-०१
Guwahati Circle, Guwah

Instructions for online Bid Submission

The Bidders are required to submit soft copies of their Bids electronically on the CPP Portal, using valid Digital Signature Certificates. The instructions given below are meant to assist the Bidders in registering on the CPP Portal, prepare their bids in accordance with the requirements and submitting their Bids online on the CPP Portal.

More information useful for submitting online Bids on the CPP Portal may be obtained at: https://eprocure.gov.in/eprocure/app.

REGISTRATION

- Bidders are required to enroll on the e-Procurement module of the Central Public Procurement Portal (<u>URL:http//eprocure.gov.in/eprocure/app</u>) by clicking on the link "Online Bidder Enrolment" on the CPP Portal which is free of charge.
- As part of the enrolment process, the Bidders will be required to choose a unique username and assign a password for their accounts.
- Bidders are advised to registration process. These would be used for any communication from the CPP Portal.
- 4) Upon enrolment, the Bidders will be required to register their valid Digital Signature Certificate (Class II or Class III Certificates with signing key usage) issued by any Certifying Authority recognized by CCA India (e.g. Sify/ NCode/ EMudhra etc.), with their Profile.
- 5) Only one valid DSC should be registered by a Bidder. Please note that the Bidders are responsible to ensure that they do not lend their DSC's to others which may lead to misuse.
- 6) Bidder then logs in to the site through the secured log-in by entering their user ID/Password and the password of the DSC / e-Token.

SEARCHING FOR TENDER DOCUMENTS

- There are various search options built in the CPP Portal, to facilitate Bidders to search active tenders by several parameters. These parameters could include Tender ID, Organization Name, Location, Date, Value, etc. There is also an option of advanced search for tenders, where in the Bidders may combine a number of search parameters such as organization Name, Form of Contract, Location, Date, other keywords etc. to search for a tender published on the CPP Portal.
- Once the Bidders have selected the tenders they are interested in they may download the required documents / tender schedules. These tenders can be moved to the respective 'My Tender' folder. This would enable the CPP Portal to intimate the Bidders through SMS / e-mail in case there is any corrigendum issued to the tender document.

3) The Bidder should make a note of the unique Tender ID assigned to each tender, in case they want to obtain any clarification / help from the Helpdesk.

Superintending Archaeologist भारतीय प्रातास सर्वश्य Archaeological Survey of India गुवासटी पण्डल, गुवासटी-०१ Guwahati Circle, Guwahati-01

PREPARATION OF BIDS

- Bidder should take into account any corrigendum published on the tender document before submitting their Bids.
- Please go through the tender advertisement and the tender document carefully to understand the documents required to be submitted as part of the Bid. Please note the number of covers in which the bid document – including the names and content of each of the document that need to be submitted. Any deviations from these may lead to rejection of the Bid.
- 3) Bidder, in advance, should get ready the Id documents to be submitted as indicated in the tender document/ schedule and generally, they can be in PDF / XLS / RAR / DWF / JPG formats. Bid documents may be scanned with 100 dpi with black and white option which helps in reducing size of the scanned document.
- 4) To avoid the time and effort required in uploading the same set of standard documents which are required to be submitted as a part of every Bid, a provision of uploading such standard documents (e.g. PAN card copy, etc.) has been provided to the Bidders. Bidders can use "My Space" of "Other Important Documents" are available to them to upload such documents. These documents may be directly submitted from the "My Space" area while submitting a Bid, and need not be uploaded again and again. This will lead to a reduction in the time required for Bid submission process.

SUBMISSION OF BIDS

- Bidder should log into the site well in advance for bid submission so that they can
 upload the Bid in time i.e. on or before the Bid submission time Bidder will be responsible
 for any delay due to other issues.
- 2) The Bidder has to digitally sign and upload the required bid documents one by one as indicated in the tender document.
- 3) Bidder has to select the payment option as "offline" to pay the tender fee / EMD as applicable and enter details of the instrument.
- Bidder should prepare the EMD as per the instruction specified in the tender documents. The original should be posted/couriered/given in person to the concerned official, latest by the last date of Bid submission or as specified in the tender documents. The details of the DD/ any other accepted instrument, physically sent, should tally with the details available in the scanned copy and the data entered during Bid submission time. Otherwise the uploaded bid will be rejected.
- 5) Bidders are requested to note that they should necessarily submit their financial Bid in the format provided and no other format is acceptable. If the price Bid has been given as a standard BOQ format with the tender document, then the same is to be download the BOQ

अधीक्षण पुरातत्वावद् Superintending Archaeologist भारतीय पुरातत्व सर्वकाण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी-वर् Guwahati Circle, Guwahati-Q1 file, open it and complete the white colored (unprotected) cells with their respective financial quotes and other details (such as name of the Bidder). No other cells should save it and submit it online, without changing the filename. If the BOQ file is found to be modified by the Bidder, the Bid will be rejected.

- The server time (which is displayed on the Bidders' dashboard) will be considered as the standard time for referencing the deadlines for submission of the Bids by the Bidders, opening of Bids etc. The Bidders should follow this time during Bid submission.
- All the documents being submitted by the Bidders would be encrypted using PKI encryption techniques to ensure the secrecy of the data. The data entered cannot be viewed by unauthorized persons until the time of Bid opening. The confidentiality of the Bids is maintained using the secured Socket Layer 128 bit encryption technology. Data storage encryption of sensitive fields is done. Any Bid document that is uploaded to the server is subjected to symmetric encryption using a system generated symmetric key. Further this key is subjected to a symmetric encryption using buyers/Bid opener's public keys. Overall, the uploaded tender documents become readable only after the tender opening by the authorized Bid openers.
- 8) The uploaded tender documents become readable only after the tender opening by the authorized Bid openers.
- 9) Upon the successful and timely submission of Bids (i.e after Clicking "Freeze Bid Submission" in the portal), the portal will give a successful Bid submission message & a Bid summary will be displayed with the Bid no. and the date & time of submission of the Bid with all other relevant details.
- 10) The Bid summary has to be printed and kept as an acknowledgement of the submission of the Bid. This acknowledgement may be used as an entry pass for any Bid opening meetings.

ASSISTANCE TO BIDDERS

- 1) Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender.
- Any queries relating to the process of online Bid submission or queries relating to CPP Portal in general may be directed to the 24x7 CPP Portal Helpdesk Number:0120-4200462, 0120-4001002.

TENDER ACCEPTANCE LETTER

(To be given on Contractor Letter Head)

Date:

To The Superintending Archaeologist Archaeological Survey of India Guwahati Circle, Guwahati

Subject:	Acceptance of Terms & Condi	tions of Tender			
Name or Worl	K:		•••••	••••	
	downloaded/ obtained the tenork' from the web site(s) namely:	der document(s)	for the	above	mentioned
As per your	advertisement, given in the above			tions of	`the tender

- 2. I/We hereby certify that I / We have read the entire terms and conditions of the tender documents from Page No.____ to ____ (including all documents like annexure(s), schedule(s) etc.), which form part of the contract agreement and I / we shall abide hereby by the terms/ conditions/ clauses contained therein.
- 3. The corrigendum(s) issued from time to time by your department/ organization to have also been taken into consideration, while submitting this acceptance letter.
- 4. I/We do hereby declare that our Firm has not been blacklisted/ debarred by any Govt. Department/Public sector undertaking.
- 5. I/We certify that all information furnished by the our Firm is true & correct and in the event that the information is found to be incorrect/ untrue or found violated, then your department/ organization shall without giving any notice or reason therefore or summarily reject the bid or terminate the contract, without prejudice to any other rights or remedy including the forfeiture of the full said earnest money deposit absolutely.

Yours Faithfully,

(Signature of the Bidder, with official Seal)

Superintending Archaeologist भारतीय पुरातस्य सर्वेक्षण Archaeological Survey of India गुवाहाटी मण्डल, गुवाहाटी-०१

Guwahati Circle, Guwahati-01