

प्रत्नकीर्त्तिमपावृणु

No. 2/25-W/2015-16-
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites item rate Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN No. & VAT Reg. No. (GRN) for execution of work as per specification. The tender document will be received up to 14.30 hours of 04.03.2016 and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
OW (Plan) to Thakurani Tilla at Paschim Pillak, South Tripura, Tripura (2015-16)	₹ 6,31,201/-	04.03.2016	Execution of work as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 15,780/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractors’s Registration certificate, PAN, VAT clearance certificate, Labour registration, etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total bill amount at source.

Superintending Archaeologist

TENDER FOR EXECUTION OF WORK

Price of Tender ₹ 500/-

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **OW (Plan) to Thakurani Tilla at Paschim Pillak, Tripura (2015-16).**

Memorandum :-

- i) Earnest Money : ₹ 15,780/-
- (ii) Security Deposit : ₹ 63,120/-
Estimated Cost : ₹ 6,31,201/-

Demand Draft No. _____
made up as under :
₹
₹

- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill As admissible

Schedule of Quantities of work

Date of opening of Tender : 04/03/2016

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at Which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
1	Providing and laying Vitrified tiles (0.60 x 0.60) in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08% and conforming to I.S.15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm thick bed of cement mortar 1:3(1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete.	121.00 sqm	Work site at Thakurani Tilla at Paschim Pillak, Tripura	Work site at Thakurani Tilla at Paschim Pillak, Tripura	Total works to be completed within 20 days		Per sqm		Tender items Sl.No.1 to 4 in Schedule is a single unit of Tender. No split up of items is entertained.
2	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture spintone/cosmos / Hexa or equivalent of size 595 x 595 mm	88.00 sqm	Do	Do	Do		Per sqm		Do

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at Which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	<p>in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main "T" runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture (Spintone / Cosmos/hexa) in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required</p>								

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at Which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	<p>Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T' , bottom exposed with 24 mm of all T-sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by engineer-in-charge.</p> <p>Note :- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/opening (cut outs) having area less than 0.30 sqm. The calcium silicate ceiling tile shall have NRC value of 0.50 (Minimum), light reflection > 85%, non - combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity <0.043 w/m 0 KC.</p>								
3	<p>Electrical Wiring :</p> <p>(a) Wiring for light/power plug with 2x4 sq.mm FR PVC insulated copper conductor single core cable in surface/recessed steel conduit alongwith 1 No. 4 sq.mm FR PVC insulated copper conductor single core cable for loop earthing as required</p>	50 mtrs.	Do	Do	Do		Per mtr		Do

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at Which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	(b) Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc. as required.	79 points	Do	Do	Do		Per point		Do
	(c) Supply & fixing following way prewired SP & N MCB distribution board of steel sheet for 240 volts. on surface/recess complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FR PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral link, earth bar, din bar, detachable gland plate, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).	1 No.	Do	Do	Do		Each		Do
	Supplying, fitting and fixing of the Electrical items as per current market rates.		Do	Do	Do		Whole Item		Do
	a. LED Light - 7 watt	12 Nos.							
	b. Ceiling Fan	4 Nos.							
	c. Ceiling Rose	48 Nos.							
	d. Light for ceiling of Museum	9 Nos.							

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at Which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
	e. 8 Module G.I. Metal box	14 Nos.							
	f. 8 Module Platinum cone Plate	14 Nos.							
						Total			

(Rupees)

.....% below/above of estimate cost.

N.B.

- Quantity of works may be increased/decreased at site.

.....
Contractor's signature with seal.

Should this tender be accepted, I/we hereby agree to abide by and fulfill all the terms and provisions of the said conditions annexed hereto so far as applicable and/or in default thereof to forfeit and pay to the President of India or successor in office the sum of money mentioned in the said conditions. A sum of ₹ * is herewith forwarded in Cash/Treasury Challan as Earnest Money. If I/we fail to commence the work specified in the above memorandum or if I/we fail to deposit the amount of security deposit specified against (ii) (a) in the above memorandum in accordance with clause 1 of the said conditions of contract, I /we agree that the said President or his successors in office, without prejudice to any other right of remedy, shall be at liberty to forfeit the said earnest money absolutely, otherwise the said President or his successors in office shall also be at liberty to cancel the acceptance of the tender if I/we fail to deposit security amount as aforesaid.

.....

* Give particulars & number.

Signature

Address

Signature of witness to signature of tenderer.

Address

Dated

The 2016

The above tender is hereby accepted by me on behalf of the President of India.

Dated


The 2016

Signature of the office by whom the tender is accepted

TERMS & CONDITIONS

1. The works/supply shall be carried out by the Contractor/Firm strictly and in accordance with the ASI, Guwahati Circle's specifications and as per direction of Engineer-in-charge.
2. The rates given for the works should be inclusive of all taxes, leads and lifts, etc. Nothing extra shall be paid over the rates quoted by the contractor/firm.
3. In case the material is not as per specification, the same shall be replaced by the contractor/firm. The department shall not be responsible for any theft or loss.
4. No payment shall be made to the contractor/firm if the materials are damaged due to natural calamities before measurement.
5. The tender must accompany the Earnest Money of ₹ 15,780/- only and cost of tender form of ₹ 500/- only in the form of Bank Demand Draft/Pay Order/Term Deposit Advice/Fixed Deposit of any Nationalized Bank in favour of Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati -1.
6. It shall be the responsibility of the contractor/firm to ensure that no damage is caused to Govt. property at the site by his/their vehicle or labour party. Cost of such damages, if any, will be assessed at the discretion of the Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle and the same will have to be made good by the contractor/firm.
7. The tender submitted on behalf of a firm shall be signed by all the partners of the firm or by a partner who is duly authorized on behalf of the firm to enter into contract. Otherwise the tender is liable to be rejected.
8. Time shall be considered as the essence of the contract. The entire work must be completed 45 days and supply must be completed within 15 days. Failing which the remaining work can be reallocated to another contractor/firm at the risk and cost of the contractor/firm with due notice to the contractor/firm.
9. All gold, silver, oil and other materials or any antiques and other similar things, which may be found, in or upon the site shall be the property of the Archaeological Survey of India. Contractor/firm shall deliver the same to such persons as the Department may from time to time appoint to receive the same.
10. Error/omission if any, shall be rectifiable with no claim.
11. No claim whatsoever on account of fluctuations in prices will be entertained.
12. If any litigation arises through labour court or labour commissioner & other court, etc. on account of litigation through labourers engaged by him, the contractor will be fully responsible. Moreover, if claim arises out of any litigation, the contractor will be responsible for payment of such claim.
13. The contractor/firm shall not be entitled to any compensation --whatsoever on account of any delay or default in the supply of materials mentioned in the schedule.
14. The Earnest money and security deposit of the successful contractor/firm will be forfeited, if he fails to comply with any of the conditions of the contract and work shall be carried out at risk and cost of the contractor/firm.
15. Overall rates shall be considered for approval of tender.
16. Any material left on the site of work after one month from the date of completion of the work shall become the property of the Govt. and no payment shall be made for it.
17. If more than one tenderer quoting the same rates are received, it will be the discretion of undersigned calling one tenderer to award the work to whom he finds suitable to do the job and his decision will be final and binding on the tenderer.
18. Work order/Supply order will be issued after receiving of security deposit.
19. The competent authority reserves the right to accept or reject any of all the tenders without assigning any reason.

Contractor's Signature with Seal


Superintending Archaeologist
Archaeological Survey of India
Guwahati Circle, Guwahati - 1