



No. 2/18-W(A)/2016-17
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **14.12.2016** and the tender document will be received up to 14.30 hours on **15.12.2016** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
SR (Plan) to Rock-Cut Temple at Maibong, Assam (2016-17)	₹ 3,49,812/-	15.12.2016	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ .8,745/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the "Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1" including Contractor's Registration certificate, PAN, VAT clearance certificate, Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.


Superintending Archaeologist

No. 2/18-W(A)/2016-17-3968

Dated 07 DEC 2016

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. *Dima Hasar* Assam.
3. The Executive Engineer, PWD, Dist. *Dima Hasar*, Assam.
4. The Sr. Conservation Assistant, ASI, Guwahati Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website "www.asi.nic.in".


Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **SR (Plan) to Rock-Cut Temple at Maibong, Assam (2016-17)**

Memorandum :-

- 1) Earnest Money : ₹ 8,745/-
 (ii) Security Deposit : ₹ 24,991/-
 Estimated Cost : ₹ 3,49,812/-
 a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
 b) Percentage to be deducted from bill

Demand Draft No.
 made up as under :

As admissible

₹

Schedule of Quantities of work

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Item	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
1.	Maintenance of the existing pathway by laying water bound macadm sub-base with brick aggregate and blinding material, earth etc. including screening, sorting and spreading to template and consolidation with light power road-roller etc, complete (payment for brick aggregate and moorum etc. to be made separately) over burnt (ghama) brick aggregate 120mm to 40mm	80.60 CuM	Work at site	Work at site	Work to be completed by 60 days		Per CuM		Tender items SL.No. 1 to 6 in Schedule is a single unit of Tender. No split up of items is entertained.
2	Cleaning jungle including uprooting of rank vegetation, grass, brush, wood, trees and saplings of girth upto 30 cm measured at a height of 1 mt. outside the periphery of the area cleared	2700.00 SqM	Work at site	Work at site	-Do-		Per SqM		Do

Suprintending Archaeologist
Archaeological Survey of India
Guwahati

- 1) Sale Price Rs.....
 2) Name of Contractor
 3) Date of Application for Tender form by Contractor.....
 4) Date of receipt of Application in Circle/Branch Office.....
 5) Date of issue of Tender paper.....
 6) Date of receipt of tender bids.....
 7) Details of cuttings, over-writings and erasings found on the tender at the time of opening.....
 8) Names and designations of Officers/Contractors present at the time of opening the Tender.....
 9) Date of opening of Tender: 15.12.2016

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
3	Earth filling the ditches area for stopping erosion of the river embankment with locally available earth including watering, ramming, consolidating and dressing complete.	91.00 CuM	Work at site	Work at site	Work to be completed by 60 days		Per CuM		-Do-
4	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like: cement mortar 1:6 (1 cement : 6 coarse sand)	25.21 CuM	Work at site	Work at site	-Do-		CuM		-Do-
5	Provision for cast iron benches over a bed of P.C.C. (1.80m x 1.50m X 0.10m) at site	02 Nos	Work at site	Work at site	-Do-		Per No		-Do-
6	Provision for supply & fixing of alluminium platform (4' x 3' x 1½') with oxidized fittings.	For whole	Work at site	Work at site	-Do-		Job		-Do-

NB: Quoting of Rates & Total cost in Col. No. 7 & 9 for all item is mandatory.

(Rupees)

N.B. : Quantity of work and materials may be increased/decreased at site.

Contractor's signature with seal.