



No. 2/18-W(A)/2016-17
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having two years experience in similar works with Archaeological Survey of India for execution of work as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **14.12.2016** and the tender document will be received up to 14.30 hours on **15.12.2016** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
SR (Plan) to Sri Sri Hayagriva Madhava Temple at Hajo, Assam (2016-17)	₹ 4,51,412/-	15.12.2016	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 11,285/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour cess at prescribed rate will be deducted from the total billed amount at source during payment.

sd/-
Superintending Archaeologist

No. 2/18-W(A)/2016-17-3883

Dated 07 DEC 2016

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Kamrup (Metro), Assam.
3. The Executive Engineer, PWD, Dist. Kamrup (Metro), Assam.
4. The Sr. Conservation Assistant, ASI, Guwahati Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”.

sd/-
Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work **SRI (Plan) to Havarivya Madhaya Temple at Hajjo, Assam (2016-17)**

Memorandum :- ₹ 11,285/-

(ii) Security Deposit : ₹ 30,071/-

Estimated Cost : ₹ 4,51,412/-

- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill

Demand Draft No. made up as under :

As admissible ₹

Schedule of Quantities of work

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
1.	Providing and fixing expanded metal 20x60 mm strands 3.25 mm wide and 1.6 mm thick for windows etc. including 62x19 mm beading of 2 nd class teak wood and priming coat with approved steel primer all complete.	84.00 SqM	Work at site	Work at site	Work to be completed by 60 days		Per SqM		Tender items Sl.No.1 to 10 in Schedule is a single unit of Tender. No split up of items is entertained.
2	Dismantling roofing including ridges, hips, valleys and gutters etc. and stacking the material within 50 meters lead of G.S.Sheet	70.20 SqM	Work at site	Work at site	-Do-		Per SqM		Do
3	Providing and fixing G.I. sheet including roof of the Mukhamandapa	70.20 SqM	Work at site	Work at site	-Do-		Per SqM		-Do-

Date of opening of Tender : 15.12.2016

(Handwritten signature)
 सहायक प्राचरक्षक
 Superintendent Archaeologist
 भारतीय प्राचरक्षक सर्वेक्षण
 आर्चायोलॉजिकल सर्वेक्षण ऑफ इंडिया
 गुवाहाटी-01

- 12) Name of Contractor
- 13) Date of Application for Tender term by Contractor
- 14) Date of receipt of Application in Circle/Branch Office
- 15) Date on issue of Tender Advertis
- 16) Date of receipt of tender papers
- 17) Details of currencies, over-writings and erasings found on the tender at the time of opening
- 18) Names and designations of Officers/Contractors present at the time of opening the Tender

Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
4	Cleaning the Garvagriha and Sealing the joint of the stone with lime mortar 1:1:1 after proper cleaning, racking the joints etc, complete	183.55 SqM	Work at site	Work at site	Work to be completed by 60 days		Per SqM		-Do-
5	Providing for mending the damaged wooden pillar (20cm dia) at Mukhamandapa with changing the broken portion by using Sal wood (local) frame including finishin etc. Salwood (local) 0.675 cum,ply wood (12mm dia) – 16.00 sqm incl. fevical, nail sand paper screws, wood fiber, clamp (iron) including labour charges	20 Nos	Work at site	Work at site	-Do-		Per No		-Do-
6	Progision for P.C.C. at top layer of existing brick on edge apron for prevention from slippery	16.28 CuM	Work at site	Work at site	-Do-		Per CuM		-Do-
7	Painting the M.S. grill in the Mukhamandapa with synthetic enamel paint	55.57 SqM	Work at site	Work at site	-Do-		Per SqM		-Do-
8	Painting the C.G.I. sheet with synthetic enamel paint	780.00 SqM	Work at site	Work at site	-Do-		Per SqM		-Do-

NB: Quoting of Rates & Total cost in Col. No. 7 & 9 for all item is mandatory.

(Rupees)

N.B. : Quantity of work and materials may be increased/decreased at site.

.....
Contractor's signature with seal.